Clim. Past, 14, 1–21, 2018 https://doi.org/10.5194/cp-14-1-2018 © Author(s) 2018. This work is distributed under the Creative Commons Attribution 4.0 License.





Deglacial to postglacial history of Nares Strait, Northwest Greenland: a marine perspective from Kane Basin

Eleanor Georgiadis^{1,2}, Jacques Giraudeau¹, Philippe Martinez¹, Patrick Lajeunesse², Guillaume St-Onge³, Sabine Schmidt¹, and Guillaume Massé²

¹Université de Bordeaux, CNRS, UMR 5805 EPOC, 33615 Pessac, France

²Université Laval, UMI 3376 TAKUVIK, Québec, G1V 0A6, Canada

³Université du Québec à Rimouski and GEOTOP Research Center, Institut des sciences de la mer de Rimouski (ISMER), Rimouski, G5L 3A1, Canada

Correspondence: Eleanor Georgiadis (eleanor.georgiadis@u-bordeaux.fr)

Received: 26 June 2018 – Discussion started: 11 July 2018 Revised: 3 November 2018 – Accepted: 27 November 2018 – Published:

Abstract. TSI CEI CE2 CE3 A radiocarbon dated marine sediment core retrieved in Kane Basin, central Nares Strait, was analysed to constrain the timing of the postglacial opening of this Arctic gateway and its Holocene evolution. This study is

- ⁵ based on a set of sedimentological and geochemical proxies of changing sedimentary processes and sources that provide new insight into the evolution of ice sheet configuration in Nares Strait. Prochecial marine sedimentation at the core site initiated ca.
- ¹⁰ grounded ice. Varying contributions of sand and clasts suggest unstable sea ice conditions and glacial activity, which subsisted until ca. 7.5 cal ka BP under the combined influence of warm atmospheric temperatures and proglacial cooling induced by the nearby Innuitian (IIS) and Greenland (GIS) ice

¹⁵ sheets. An interval rich in ice-rafted debris (IRD) is interpreted as the collapse of the ice saddle in Kennedy Channel ca. 8.3 cal ka BP that marks the complete opening of Nares Strait and the initial connection between the Lincoln Sea and northernmost Baffin Bay. Delivery of sediment by icebergs

²⁰ was strengthened between ca. 8.3 and ca. 7.5 cal ka BP following the collapse of the buttress of glacial ice in Kennedy Channel that triggered the acceleration of GIS and IIS fluxes toward Nares Strait. The destabilisation in glacial ice eventually led to the rapid retreat of the GIS in eastern Kane ²⁵ Basin at about 8.1 cal ka BP as evidenced by a noticeable change in sediment geochemistry in our core. The gradual decrease in carbonate inputs to Kane Basin between ~ 8.1 and ~ 4.1 cal ka BP reflects the late deglaciation of Washington Land. The shoaling of Kane Basin can be observed in our record by the increased winnowing of lighter particles as the glacio-isostatic rebound brought the seabed closer to subsurface currents. Reduced iceberg delivery from 7.5 to 1.9 cal ka BP inferred by our dataset may be linked to the retreat of the bordering ice sheets on land that decreased their number of marine termini.

1 Introduction

The Holocene history of Nares Strait, Northwest Greenland, has remained somewhat cryptic despite investigations during the past 4 decades (e.g. Blake Jr. 153, 7, 9; Kelly and Bennike, 1992; Mudie et al., 2004; Jennings et al., 2011.). 40 Nares Strait is a key gateway for Arctic seawater and ice toward the Atlantic Ocean, contributing to up to half of the volume of water transported through the Canadian Arctic Archipelago (CAA), which provides fresh water to the Labrador Sea and influences deep water formation (Belkin et 45 al., 1998; Münchow et al., 2006; McGeehan and Maslowski, 2012). Nares Strait supplies one of the most productive regions of the Arctic, the North Water Polynya (NOW), with nutrient-rich Pacific water (Jones et al., 2003; Jones and Eert, 2004) and maintains its very existence by trapping sea and 50 calved glacial ice in ice arches in the north and south of the strait (Melling et al., 2001; Mundy and Barber, 2001).

Despite the importance of Nares Strait, intrinsic investigations into its late Pleistocene history, which is intimately linked with the dynamics of the bordering Innuitian (IIS) 55 and Greenland (GIS) ice sheets, are relatively sparse and much of the knowledge relies on land-based studies. Debate initially surrounded early studies into glacial configuration in the CAA with some authors concluding that the CAA channels were not blocked during the Last Glacial ⁵ Maximum (LC) (Franklin Ice Complex theory; e.g. Eng-

- land, 1976 [153] ______hile others argued that the IIS coalesced with the bordering Greenland and Laurentide ice sheets (e.g. Blake Jr., 1970). The presence of erratic boulders originating from Greenland on Ellesmere Island (England, 1999),
- ¹⁰ cosmogenic nuclide surface-exposure dating (Zreda et al., 1999), and radiocarbon dating ar mollusc shells (e.g. Bennike et al., 1987; Blake Jr. 1992; Kelly and Bennike, 1992) finally settled the argument in favour of the latter narrative by supporting the coalescence of the IIS and GIS
- ¹⁵ along Nares Strait between 19 and ca. 8 ¹⁴C ka BP (~ 22– 8.2 cal ka BP, $\Delta R = 240$). England (1999) reviewed all landbased evidence available at that time and proposed a complex deglacial history of Nares Strait, featuring the late break-up of glacial ice in central Nares Strait (i.e. Kennedy Channel).
- ²⁰ These land-based studies have been complemented by Jennings et al. (2011) and Mudie et al. (2004) investigations of marine sediment cores collected in Hall Basin, northernmost Nares Strait, which record a change in a number of environmental proxies ca. 8.3 ¹⁴C ka BP (~ 8.5 cal ka BP,
- ²⁵ $\Delta R = 240$). More recently, the geophysical mapping of submarine glacial landforms by Jakobsson et al. (2018) provided additional insight regarding the retreat of Petermann Glacier in Hall Basin, and new surface-exposure dating on moraines in Washington Land demonstrates that the Humboldt Glacier,
- ³⁰ eastern Kane Basin, abandoned a previous position of stability ca. 8.3 ± 1.7 ka BP (Reusche et al., 2018). To date, little is known about the downstream consequences of the opening of the strait, despite the recovery of multiple marine archives in northernmost Baffin Bay (Blake Jr. et al., 1996; Levac et
- ³⁵ al., 2001; Knudsen et al., 2008; St-Onge and St-Onge, 2014). Several aspects of the evolution of northernmost Baffin Bay have been explored with regards to ice sheet retreat in the area (Blake Jr. et al., 1996), ice sheet dynamics (St-Onge and St-Onge, 2014), and changes in sea ice conditions and marine
 ⁴⁰ productivity during deglacial and postglacial times (Levac et al., 2001; Knudsen et al., 2008; St-Onge and St-Onge, 2014). Unfortunately, however, these archives do not cover a continuous record of the Holocene and the sediments deposited around and before the opening of the strait were not recov-

⁴⁵ ered or are unable to provide any further information on the timing and consequences of the event.

Here we present sedimentological, geochemical, and geochronological data obtained from a 4.25 m long marine sediment core (AMD14-Kane2b) retrieved in Kane Basin, ⁵⁰ central Nares Strait. This core prevides a continuous sedimentary record spanning the las calka BP, i.e. from the inception of the Early Holocene retreat of the GIS and IIS in Nares Strait to modern times. Our set of sedimentological and geochemical records derived from this study presents ⁵⁵ the first offshore evidence of an ice-free environment in Kane Basin in the Early Holocene and offers a unique opportunity to explore the local dynamics of ice sheet retreat leading to the opening of the strait and the establishment of the modern oceanographic circulation pattern.

60

2 Regional settings

Nares Strait is a long (530 km) and narrow channel separating Northwest Greenland from Ellesmere Island, Arctic Canada, connecting the Arctic Ocean to the Atlantic Ocean in Baffin Bay (Fig. 1). Kane Basin is the central, wide (120 km large at its broadest point, totalling an area of approximately 27 000 km²), and shallow (220 m deep) basin within Nares Strait. It separates Smith Sound (600 m deep, 50 km wide) in the south of the strait from Kennedy Channel (340 m deep, 30 km wide) in the north. A smaller but deeper basin, Hall Basin (800 m deep), where the Petermann Glacier terminates, connects Kennedy Channel to the Robeson Channel (400 m deep, 21 km wide) in the northernmost sector of the strait.

The oceanographic circulation in Nares Strait consists of a generally southward-flowing current driven by the barotropic gradient between the Lincoln Sea and Baffin Bay (Kliem and 75 Greenberg, 2003; Münchow et al., 2006), while the baroclinic temperature balance generates strong, northerly winds that affect surface layers (Samelson and Barbour, 2006 Münchow et al., 2007; Rabe et al., 2012). The relative influence of the barotropic vs. baroclinic factors that control the 80 currents in Nares Strait is highly dependent on the presence of sea ice that inhibits wind stress when landfast (Rabe et al., 2012; Münchow, 2016). Long-term ADCP measurements of flow velocity record average speeds of $20-30 \,\mathrm{cm \, s^{-1}}$ in Kennedy Channel (Rabe et al., 2012; Münchow et al., 2006) 85 and $10-15 \text{ cm s}^{-1}$ in Smith Sound (Melling et al., 2001) with the highest velocities measured in the top 100 m of the water column. Strong currents peaking at 60 cm s^{-1} have been measured instantaneously in Robeson Channel (Münchow et al., 2007). The speed of the flow decreases in the wider sections of Nares Strait. A northward current has been shown to enter Kane Basin from northern Baffin Bay (Bailey, 1957; Muench, 1971; Melling et al., 2001; Münchow et al., 2007). Temperature and salinity isolines imply that an anticlockwise circulation takes place in the surface layers of Kane Basin, 95 while the deeper southward flow of Arctic water is channelled by bottom topography and concentrated in the basin's western trough (Muench, 1971; Moynihan, 1972; Münchow et al., 2007).

Sea ice concentration in Nares Strait is usually over 80 % ¹⁰⁰ from September to June (Barber et al., 2001). The state of the ice varies between mobile (July to November) and fast ice (November to June). The unique morphology of the strait leads to the formation of ice arches in Nares Strait when sea ice becomes landfast in the winter. The ice arches ¹⁰⁵ are a salient feature in the local and regional oceanography of Nares Strait: they not only block sea ice from drifting




Figure 1. ISSUE: natic circulation in the Canadian and northern Greenland sectors of the Arctic Ocean (**a**) and within Nares Strait (**b**). The location of core AMD14-Kane2b is marked by a cross. Blue arrows represent Arctic water and red arrows predominantly Atlantic water. WGC: West Greenland Current, BBC: Baffin Bay Current. 1 – Smith Sound; 2 – Kennedy Channel; 3 – Hall Basin; 4 – Robeson Channel, 5 – Humboldt Glacier; 6 – Petermann Glacier; 7 – Inglefield Land; 8 – Washington Land; 9 – Judge Daly Promontory; 10 – Bache Peninsula; 11 – Johan Peninsula; 12 – Agassiz Ice Cap.

southward in the strait, sustaining the existence of the NOW Polynya (Barber et al., 2001), but they also control the export of low-salinity Arctic water into Baffin Bay (Münchow, 2016). The main iceberg sources for the strait are Petermann 5 Glacier in Hall Basin and Humboldt Glacier in Kane Basin, both outlets of the GIS.

The Greenland coast bordering Kane Basin is relatively flat. In Inglefield Land the Precambrian basement is exposed, displaying supracrustal crystalline rocks and meta-10 morphic rocks, essentially reported as aluminous metasediments and gneisses or granitoid gneisses, with some references to quartzite (Fig. 2, Koch, 1933; Dawes, 1976 Dawes and Garde, 2004 Harrison and Oakley 2006, ISI and references therein). Dawes and Garde, 1511 - 04) pos-15 tulated that this Precambrian basement also underlies the 100 km wide Humboldt Glacier, a claim that is supported by the dominance of crystalline material delivered in modern glacimarine sediments in front of the Humboldt Glacier (Fig. 2, Kravitz, 1976). To the north, the Precambrian base-20 ment in Washington Land is overlaid by Cambrian, Ordovician, and Silurian dolomites, limestones, and evaporites (Koch, 1929a, b; Harrison et al., 2006, and references therein). The Ellesmere shore of Kane Basin rises abruptly from sea level and is punctured by narrow fjords, penetrat-25 ing inland for nearly 100 km (Kravitz, 1982). In southern Kane Basin, the same Precambrian crystalline rocks outcrop to form the Ellesmere–Inglefield Precambrian Belt. The central and northern sectors of Ellesmere Island's coast mainly comprise Cambrian to Devonian carbonates and evaporates. Fluviodeltaic quartz sandstone, volcanistic sandstone, minor arkose, and sometimes coal are found in the Paleogene Eureka Sound sequence that occurs along the western coast of Kane Basin, on the Ellesmere Island flank of Kennedy Channel, and on Judge Daly Promontory (Christie, 1964, 1973; Kerr, 1967, 1968; Miall, 1982; Oakey and Damaske, 2004). ³⁵ Coal-bearing Paleogene clastics also occur along the coast of Bache Peninsula and in morainic deposits on Johan Peninsula in southwestern Kane Basin (Fig. 2, Kalkreuth et al., 1993).

Kravitz (1976) described modern sedimentation in Kane Basin according to three main provinces defined on the basis of mineralogical and grain size characteristics. The first province covers the eastern, central, and southern part of the basin in which the predominant crystalline clay and silt sediments are water-transported off Humboldt Glacier and Inglefield Land. The second province, in the west of the basin, includes a higher fraction of ice-transported materials, mostly carbonates with clastic debris occurring in the deeper trough. Northern Kane Basin makes up the third province in which water-transported, mostly carbonate sediments from Washington Land are deposited in its northernmost part, while 50 ice-transported crystalline particles are more common in the southern part of this province.




Figure 2. Geology of Northwest Greenland and Ellesmere Island along Nares Strait. Adapted from Harrison et al. (2011).

3 Material and methods

Sediment core AMD14-Kane2b was retrieved at 217 m of water depth in Kane Basin, Nares Strait (79°31.140' N; 70°53.287' W) during the 2014 ArcticNet expedition of 5 the CCGS *Amundsen*. This core was collected with a

the CCGS Amunasen. This core was conected with a wide-square section ($25 \text{ cm} \times 25 \text{ cm}$) gravity corer (Calypso Square or "CASQ") and immediately subsampled onboard using large U chann

3.1 Sedimentological analyses

- ¹⁰ The description of the various lithofacies was based on the visual description of the core and high-resolution images using a computed tomography (CT) scanner (Siemens SOMATOM Definition AS+ 128 at the Institut National de la Recherche Scientifique, Quebec, Canada). Changes in sediment density ¹⁵ were estimated from variations in the CT numbers, which
- were processed according to Fortin et al. (2013). To complement CT analyses, a series of thin sections covering two intervals were sampled across major lithological changes toward the base of the core (425–405 and 373.5–323.5 cm) in
- ²⁰ order to visualise the internal structure and examine the nature of these facies. The thin sections were prepared according to Zaragosi et al. (2006). Grain size analyses were performed at intervals of 2 to 4 cm throughout the archive. A Malvern 2000 laser sizer was used to determine the relative
- ²⁵ contribution (expressed as % of particles) of clay and colloids (0.04–4 μ m), silt (4–63 μ m), and sand (63–2000 μ m) within the <2 mm fraction. The same samples were also subjected to wet sieving through 63, 125, and 800 μ m meshes in or-

der to determine the weight fraction of sands and identifiable ice-rafted debris (IRD), expressed as % weight of the bulk ³⁰ dry sediment.

3.2 XRF core scanning

High-resolution (0.5 cm) X-ray fluorescence (XRF) scanning was conducted along the archive using an Avaatech XRF core scanner. The semi-quantitative elemental composition of the 35 sediment was measured throughout the whole archive with the exception of two units, which contain large clasts. Measurements were acquired with generator settings of 10, 30, and 50 kV in order to detect elements in the range of Al to Ba. Elemental ratios or normalisation to the sum of all elements 40 except Rh and Ag, whose counts are biased during data acquisition, were used to minimise the effects of grain size and water content on elemental counts (Weltje and Tjallingii, 2008 **T**RF core-scanner-derived elemental ratios have been used as a time-efficient method to assess down-core varia- 45 tions in grain size (e.g. Guyard et al., 2013; Mulder et al., 2013; Bahr et al., 2014) and/or sediment sources for detrital material in similar high-latitude locations (e.g. Møller et al., 2006; Bervid et al., 2017). The applicability of this approach in Kane Basin is tested in the present study by using Ti / F and Fe / Ca as proxies for grain size and sediment source, respectively. We also demonstrate a correlation between normalised K counts and clay content in core AMD14-Kane2b.




Figure 3. 210 Pb_{XS} and 137 Cs profiles in AMD14-Kane2b box core (circles). 210 Pb_{XS} data points in the top part of AMD-Kane2b gravity core have been shifted to obtain the best correspondence of the plots, yielding a material loss of 4 cm at the top of the gravity core.

3.3 Chronology and radiocarbon dating in Nares Strait

The chronology is based on a set of 18 radiocarbon ages obtained from mixed benthic foraminifera samples and unidentified mollusc shells. The core top is dated at -5 years BP 5 (1955 CE) based on ²¹⁰Pb measurements and a comparison with the ²¹⁰Pb profile (Fig. 3) obtained from a box core collected at the same coring site.

Reservoir ages in Nares Strait are difficult to assess owing to the scarcity of pre-bomb specimens in collections ¹⁰ of marine shells from the area. Only three molluscs were dated in Nares Strait with ΔR ranging between ~ 180 and ~ 320 years, comparing relatively well with molluscs from the western sector of northernmost Baffin Bay (ΔR of ~ 140 and ~ 270), while molluscs collected near Thule, North-¹⁵ west Greenland, yielded negative ΔR (McNeely et al., 2006).

Coulthard et al. (2010) proposed a regional ΔR for the CAA of 335 years based on the McNeely et al. (2006) dataset of pre-bomb radiocarbon-dated molluscs and taking into account the general oceanographic circulation in the CAA.

²⁰ However, unlike in other passages of the CAA, which present shallow sills at their southern extremities, younger Atlantic water from Baffin Bay enters Nares Strait – or at least Kane Basin – from the south (Bailey, 1957; Muench, 1971; Münchow et al., 2007). We thus choose to correct ¹⁴C ages in this ²⁵ study with the average ΔR of the three pre-bomb collected mollusc shells in Nares Strait, i.e. 240 ± 51 years, bearing in mind that reservoir ages are likely between 0 and 335 years and may have changed through time as a consequence of the major oceanic reorganisation in Nares Strait. Radiocar-³⁰ bon dating in Nares Strait is further complicated by the proximity of old carbonate rocks that are prone to introducing additional uncertainties in the ¹⁴C ages yielded by depositfeeding molluscs (England et al., 2013). The non-systematic discrepancies between ages yielded from deposit feeders and those from suspension-feeding molluscs - the so-called Port- 35 landia effect (England et al., 2013) - cannot be corrected. However, this represents a greater challenge for land-bound studies that pinpoint the timing of the deglaciation of a given location based on the oldest mollusc found in that location. In contrast, when establishing the age model of sediment cores, 40 the age vs. depth relationship reveals any outliers that can be identified as either (1) remobilised by ice rafting, slumping, or bioturbation or (2) potentially affected by the Portlandia effect. Hence, we deem the Portlandia effect to be of minor concern in the establishment of the age model in this 45 study despite the possible inclusion of deposit feeders in our radiocarbon dataset. The ¹⁴C ages were calibrated with the Marine13 curve (Reimer et al., 2013) using Calib7.1 (Stuiver et al., 2018) with marine reservoir age correction of 640 years ($\Delta R = 24$) We computed an age-depth model 50 for core AMD14-Kane2b based on radiocarbon-dated material using CLAM 2.2 (Blaauw, 2010) as a smooth spline with a smoothing level of 0.4 and assuming that a 20 cm long clast-rich deposit (300-320 cm) was deposited near instantaneously at the scale of our chronology. 55

4 Results and interpretations

4.1 Age model and sedimentation rates in core AMD14-Kane2b

According to our chronology, core AMD14-Kane2b covers the last 9.0 cal ka BP (Fig. 4). The comparison of the ²¹⁰Pb 60 profiles of core AMD14-Kane2b and the box core collected at the same location reveals the relatively good recovery of the topmost sediments in the CASQ core permitted by the large diameter of this corer (sediment loss of ~ -1 ; Fig. 3). Fourteen of the ¹⁴C ages yielded consistent values along a 65 smooth spline, while four outlying radiocarbon ages were excluded from the age model. Only one mollusc fragment was dated (at 301.5 cm) and yielded an age of >43 ka; it is thus clearly remobilised (Table 1). A whole mollusc shell at 238.5 cm yielded a radiocarbon age about 1 kyr older than 2 70 pected and is the only specimen we suspect to be affected the Portlandia effect. Two mixed benthic foraminifera samples yielded ages older than expected and most likely include older specimens.

Major changes in depositional environments, most particularly during the time interval corresponding to the lower half of our sediment core, explain the wide range of sedimentation rates. High sedimentation rates are observed between the base and ~ 250 cm, where they decrease from ~ 220 to 30 cm ka⁻¹, and after which sedimentation rates increase to reach 50 cm ka⁻¹ at 120 cm before decreasing again to ~ 204 cm ka⁻¹ at the top of the core.




Figure 4. Core AMD14-Kane2b age model (a) and sedimentation rates (b). The age model is a smooth spline computed using CLAM 2.2 with a smoothing level of 0.4 based on selected radiocarbon dates presented in Table 1. 1σ uncertainty is shown in grey. ¹⁴C ages excluded from the age model (time reversals) are crossed out in red.

Table 1. AMS radiocarbon ages on selected carbonate material. Asterisks indicate data that were not used in the age model. MBF: mixed benthic foraminifera, MS: unidentified mollusc shell.

Laboratory code	Dated material	Depth (cm)	¹⁴ C age (a BP)	Median probability age (cal a BP) $\Delta R = 0$	$1\sigma \Delta R = 0$ (cal a BP)	Median probability age (cal a BP) $\Delta R = 240$	$1\sigma \Delta R = 240$ (cal a BP)
SacA-46000	MS	58.5	3150 ± 35	2932	2869-2984	2700	2673-2736
UGAMS-24304	MS	59	3125 ± 25	2900	2854-2941	2683	2655-2720
UGAMS-24305	MS	62	3010 ± 25	2775	2739-2802	2502	2428-2575
SacA-46003	MBF	122	$6125\pm45^*$	6555	6494–6617	6205	6259-6356
UCIAMS-173009	MS	139	4540 ± 20	4760	4764-4809	4427	4392-4453
UGAMS-24307	MS	186	5445 ± 25	5823	5780-5876	5572	5541-5602
UGAMS-24295	MS	207.5	6005 ± 25	6417	6382–6458	6005	6168-6240
UCIAMS-173006	MS	238.5	$8175\pm20^*$	8651	8595-8690	8389	8363-8411
SacA-46002	MBF	251.5	7250 ± 60	7714	7649–7780	7503	7451–7555
SacA-45999	MBF	273.5	7870 ± 50	8336	8290-8388	7870	8026-8147
Beta-467584	MBF	297.5	7980 ± 30	8433	8388-8469	8215	8167-8259
UGAMS-24294	MS fragment	301.5	$43700\pm225*$				
Beta-467583	MBF	310.5	$9380\pm30^*$	10210	10180-10234	9907	9821-10001
Beta-467583	MBF	327.5	8160 ± 30	8633	8577-8685	8379	8347-8405
SacA-46001	MBF	333.5	8200 ± 60	8709	8587-8796	8422	8358-8482
UCIAMS-173007	MS	358.5	8450 ± 20	9050	9002-9080	8703	8637-8752
UCIAMS-173008	MS	362.5	8520 ± 20	9149	9094-9205	8840	8773-8908
UGAMS-24296	MS	407.5	8640 ± 30	9318	9272–9373	8998	8968-9021

4.2 Relationship between XRF data, grain size, and sediment sources

occur in the eastern province of the basin with provenance from the Humboldt Glacier and Inglefield Land, whereas carbonates in its western sector are sourced from Ellesmere Island or from Washington Land in its northern sector (Fig. 2, Kravitz, 1976). The geochemical composition of modern 10

In modern sediments, the spatial variability of sediment geochemistry in Kane Basin is likely related to their provenance. 5 Heavy crystalline minerals (e.g. garnet and orthopyroxene)

Clim. Past, 14, 1-21, 2018

sediments varies likewise, with notably high concentrations of Fe and Zn in the eastern sector of Kane Basin (Kravitz, 1994). Although the exact chemical variability of the source geological units is not known at present, we consider the

- 5 sedimentary rocks from eastern Kane Basin and northern Nares Strait likely to be rich in Ca, whereas higher concentrations of Fe, Si, and K presumably characterise the crystalline rocks of the Elle ____re–Inglefield Precambrian Belt. We propose the use of F_{c} a in our study to follow the po-
- 10 tential erosion of rocks from under the Humboldt Glacier and Inglefield Land (presumably Fe-rich) and from Ellesmere Island (presumably Ca-rich). We then infer the position of the GIS and IIS in relation to the core site and the geological units. It can be noted, however, that a direct link between the
- 15 XRF-derived elemental composition of the sediment and the nearby geological units can be compromised by the ubiquitous nature of certain elements in crystalline and sedimentary rocks, along with the sensitivity of elemental signals to grain size when using XRF core scanning. The interpretations of
- 20 our XRF dataset in terms of sediment sources warrant confirmation by future research into the mineral associations in core AMD14-Kane2b (Caron et al., 2018 position of the GIS margin in Kane Basin exposed hereafter, however, is unlikely to be affected by the outcome of the lat-
- 25 ter study owing to our sedimentological and grain size studies that provide evidence for the distance of the ice margin to the coring site.

XRF counts in core AMD14-Kane2b are largely dominated by Ca and Fe, which are anticorrelated. Our records

30 show a good correlation between normalised K counts and clay content in the $<2 \,\mathrm{mm}$ fraction (laser diffraction grain size data) with a correlation factor of $r^2 = 0.57$ that reaches $r^2 = 0.73$ by removing nine outlying data points from the total 150 samples an ed by laser diffraction (Fig. 6, Fig. S1 ³⁵ in the Supplement). Likewise, ther an excellent correlation between silt content and the **L** K ratio from the

- XRF elemental composition data. The correlation factor between % silt and Ti / K is $r^2 = 0.35$, but rises to $r^2 = 0.84$ by removing nine outlying data points (seven of which are dif-
- ⁴⁰ ferent to those removed to improve the correlation between K counts and % clay, mainly from lithological units 3A and 3C presented hereafter). The similar trends of normalised K counts and the Fe / Ca ratio in units 2, 3, 4, and 5 suggest that the clay content and sediment source may be linked or 45 respond to the same controlling factor.

4.3 Lithological units and sedimentological processes

The chirp 3.5 kHz sub-bottom profile obtained prior to core recovery is shown in Fig. 5. Given the good recovery of recent sediments at the top of core AMD14-Kane2b (Fig. 3), 50 we place the top of core AMD14-Kane2b at the sedimentwater interface on this profile. Assuming an acoustic velocity of $1500 \,\mathrm{m \, s^{-1}}$, the base of the core reached a coarse unit (unit 0) shown to continue below the retrieved sediment (Fig. 5), which is likely to have stopped the penetration of the CASQ corer. The high level of backscatter, discontinu- 55 ous reflectors, and lack of internal coherence in unit 0 are all discriminant acoustic characteristics of diamicton, which contains high amounts of unsorted clasts in a clay to silt trix (Davies et al., 1984). Given the thickness of unit 0^{-1} interpret this diamicton as being either subglacial till or the 60 first glacimarine sediments deposited during the retreat of the marine-based ice sheet margin.

Based on CT scans and grain size records, five lithological units were defined for core AMD14-Kane2b, each corresponding to specific depositional environments (Fig. 6, Ta- 65 ble 2). The sedimentological processes at play will be examined here, while their environmental significance will be considered in the discussion section of this paper.

Unit 1 (425–394 cm, ca. 9.0 cal ka BP) encompasses three subunits of distinct lithological nature.

Subunit 1A (425-416 cm) consists of high-density, occasionally sorted coarse sediment in a clayey matrix, interbedded with thinner layers of lower-density silty clay (Table 2). The base of the coarser laminations shows erosional contact with the underlying finer beds (thin sections in Table 2). 75 Grain size analysis reveal large amounts of sand (26 %-39 %) and silt (24%-32%) in the <2 mm fraction in this interval. The relative weight of the $125-800 \,\mu\text{m}$ and $> 800 \,\mu\text{m}$ fractions also contributes considerably to the overall weight of the sediment (18 % and 11 %, respectively). 80

These laminated deposits display all the characteristic of ice-proximal deposits (List, 1982; Ó Cofaigh and Dowdeswell, 2001). Unit 1A was most likely deposited at the ice sheet margin some ~ 9.0 cal ka ago, according to a dated mollusc shell at the base of unit 1C and given the very 85 high sedimentation rates in ice-proximal environments.

Subunit 1B (416-410 cm) displays a sharp decrease in sediment density with the replacement of sand by finer material (60% clay in the < 2 mm fraction; Fig. 6, Table 2). While subunit 1B encompasses some clasts (CT scan in Table 2), 90 the amount of sand and silt actually present in 1B may be lower than reflected by the laser diffraction and wet-sieving data, as the analysed samples likely included coarser material from the overlying and underlying subunits 1A and 1C. XRF data for subunit 1B show high Fe / Ca and Ti / Ca ratios and 95 low Ca counts.

The finer grain size in this subunit is indicative of a change from an ice margin to an ice-proximal glacimarine environment in which suspended matter settling from turbid meltwater plumes is likely the main depositional process (Elverhøi 100 et al., 1980; Syvitstki, 1991, Dowdeswell et al., 1998; Hogan et al., 2016), although the limited thickness (4 cm) of subunit 1B is rather unusual for this process. The geochemical grain size tracers Ti / K and K show poor correlation with the relatively low silt and high clay content in subunit B2. While 105 K counts are low, Ti / K ratios are high, which may suggest a high-energy environment, supporting the previous hypothesis of an ice-marginal environment in which meltwater pulses




Figure 5. 3.5 kHz chirp profile across the coring location. Core AMD14-Kane2b is represented by the orange box. Vertical scale in s (TWT) with depth conversion assuming 100 ms (TWT) = 75 m.

can transport relatively large particles. High Fe / Ca is evocative of an eastern origin of the sediments in subunit 1B, implying that the GIS was close to the core site.

Subunit 1C (410–394 cm) interrupts the fine-grained sedi-⁵ mentation with a sharp increase in the occurrence of outsized clasts. The coarser fractions account for a significant part of the sediment (up to 18 % for both the > 800 and 800–125 μ m fractions) within a dominantly clayey matrix. Sediment density in subunit 1C increases to reach values similar to those ¹⁰ observed in subunit 1A. However, unlike subunit 1A, subunit

1C is not laminated and clasts are larger (frequent gravel) and ungraded.

Given the high gravel content in subunit 1C, we consider the clasts to have been predominantly iceberg-rafted to the

- ¹⁵ core location rather than sea-ice-rafted (Pfirman et al., 1989; Nürnberg et al., 1994). These large amounts of IRD among very poorly sorted material can be interpreted as (1) increased iceberg calving rates, (2) changes in the delivery of sediment by icebergs (increased melting of or dumping from ²⁰ icebergs), or (3) a severe decrease in the delivery of finer par-
- ticles that increases the apparent contribution of clasts to the sediment (Hogan et al., 2016, and references therein).

Unit 2 (394–320 cm, 9.0–8.3 cal ka BP) can be divided into two subunits based on grain size and density. The relative ²⁵ weight of the coarse fraction varies throughout unit 2 with a generally decreasing trend.

Subunit 2A (394–370 cm, 9.0–8.8 cal ka BP) is composed of poorly sorted, bioturbated sediment ($\sim 55\%$ clay and $\sim 38\%$ silt in the <2 mm fraction) with varying contribu-³⁰ tions of coarser material (between ~ 0 and 5%) and occasional lonestones (Fig. 6, Table 2). Sediment density is fairly high, but gradually decreases toward the top of subunit 2A. Ti / K decreases gradually in this subunit, mirroring the decrease in density and opposing the increase in K counts. The Fe / Ca ratio is low at the base of subunit 2A before increasing upward in this subunit.

The dominance of fine particles in subunit 2A with occasional clasts points to a delivery by meltwater plumes and iceberg rafting. The decreasing Ti / K and silt content along with increasing K counts and clay suggests a growing distance of the ice margin from the core site since coarser silts and Ti-bearing minerals settle closer to the ice margin, while clay particles tend to sink in more ice-distal locations (Dowdeswell et al., 1998; Ó Cofaigh and Dowdeswell, 2001). Increasing Fe / Ca in subunit 2A may indicate a growing contribution of Paleozoic carbonates on Ellesmere Island in western Kane Basin and/or Washington Land in northern Kane Basin (Fig. 2).

The sediments of subunit 2B (370-320 cm, 8.9-8.3 cal ka BP) have a lower density and a lower sand ⁵⁰ and silt content than those of subunit 2A, which are a content reaches maximum values to an average 6 Scarce lonestones occur in this subunit and the sediment appears to be faintly laminated. Four biogenic carbonate samples, both mollusc and mixed benthic foraminifera samples, ⁵⁵ were dated in subunit 2B, and high sedimentation rates of ~130 cm ka⁻¹ decreasing upward to 90 cm ka⁻¹ were calculated from the age model (Table 1, Fig. 4). Subunit B2 is characterised by low Ti / K and high K and Fe / Ca.

These high sedimentation rates, substantial concentrations ⁶⁰ of clay, and the slightly laminated aspect of subunit 2B indicate that these sediments were mainly delivered by melt-

E. Georgiadis et al.: Deglacial to postglacial history of Nares Strait, Northwest Greenland




Figure 6. Sedimentological results and elemental signature of the detrital fraction of core AMD14-Kane2b. Laser diffraction grain size repartition (<2 mm fraction) is shown as % sand, silt, and clay. Normalised Zr counts are not shown but their profile is similar to that of Ti.

water plumes in a more distal glacial setting (Ó Cofaigh and Dowdeswell, 2001). Relatively high Fe / Ca possibly reflects an increased contribution from eastern Kane Basin gneisses.

Unit 3 (320–300 cm, 8.3 cal ka BP) stands out as a clast-⁵ rich interval. The high density of this unit is comparable to that of subunits 1A and 1C. CT scans and thin sections reveal the presence of a finer-grained horizon enclosed between coarser material, dividing this interval into three subunits (Table 2). Subunit 3A (320–313 cm) corresponds to the lower clastrich subunit. A significant portion of the bulk rediment is attributed to 800–125 μ m sand (17 % wtfsts) = 1 > 800 μ m sand (up to 7 % wt), while the clay matrix contributes to ~ 53 % of the < 2 mm fraction. Ti / K ratios are high, whereas Fe / Ca ratios and K have significantly decreased compared 15 to the underlying subunit 2B (Fig. 6).

The high clast content and absence of grading suggest that the sediments forming subunit 3A were ice-rafted and deposited at the core location (Ó Cofaigh and Dowdeswell,

Table 2. Details of CT scans and thin sections for each lithologic unit of core AMD14-Kane2B and summarised descriptions and interpreta-
tions. The paleo-environmental implications discussed in this study have been outlined here.

CT scan	Lithostratigraphic representation	Thin sections	Unit	Description	Sedimentary process	Paleo-environmental implications	
90 cm 22	· }		5B	Silty-clay matrix. Few lonestones.	Hemipelagic sedimentation/ limited contribution of settling from meltwater plumes. Limited ice rafting.	Glacial distal/hemipelagic sedimentationn. Winnowing from strong subsurface currents. Moderate calving following the decceleration of glacial ice fluxes. Severe sea ice conditions.	
250 cm		, , , ,	5A	Silty-clay matrix. Less frequent lonestone in comparison to unit 4.	Less deposition from meltwater plumes. Less ice rafting.	Greater distance of the ice margin to the core site (i. e. retreat of the GIS in eastern Kane Basin). Decceleration of glacial fluxes and/or increased sea ice.	7.5 cal ka BP
280 cm			4	Dominant clay. Frequent lonestones.	Settling from meltwater plumes. Frequent ice rafting	Distal glacial marine environment (O Cofaigh & Dowdesweil, 2001). Increased calving rates following the collapse of the glacial buttress in Kannedy Channel. Limited sea ice.	8.1 cal ka BP
300 cm			3C	Unsorted silt to gravel/ pebble in a clay matrix. Absence of grading	Iceberg-rafted sediment	Increased calving rates resulting from accelerated glacial fluxes following the collapse of the glacial buttress in Kennedy Channel (MacGregor et al., 2016).	8.3 cal ka BP
310 cm -			3В	Faintly laminated silty sediment.	High-energy water transport predominant, minor ice-rafted debris	Entrainment of sediment from northern Nares Strait associated with the establishment of the Hall Basin-Kane Basin connection through Kennedy Channel.	
320 cm			3A	Unsorted silt to gravel/ pebble in a clay matrix. Absence of grading	Iceberg-rafted sediment	Collapse of the GIS/IIS ice saddle in Kennedy Channel.	
340 cm	ς · . 		2B	Dominant clay, slightly laminated. Lonestones less frequent in comparison to subunit 2A.	Settling from meltwater plumes. Ice rafting less frequent.	Distal glacial marine ervironment (Ó Cofaigh & Dowdeswell, 2001). Increasing sea ice occurrence.	8.3 cal ka BP
380 cm	·		2A	Gradually finer material. Frequent lonestones.	Settling from meltwater plumes. Occasional ice rafting	Growing distance of the ice margin to the core site. Limited sea ice occurrence.	8.9 cal ka BP
400 cm			1C	Unsorted silt to gravel/ pebble in a clay matrix. Absence of grading	Iceberg-rafted sediment	Release of accumulated glacial ice flux following the break-up of sea ice and resulting in intense iceberg calving (Reeh et al., 2001).	9.0 cal ka BP
410 cm			1B	Finely laminated sediment. Few or no lonestones	Settling of suspended sediment from meltwater plumes. Little to no ice rafting.	Proximal glacial marine environment under severe sea ice confitions (O Cofaigh & Dowdeswell, 2001) which may be related to the 9.3-9.2 cold event (Axford et al., 2009, Fisher et al., 2011)	
420 cm		1A	Interbedded coarse and fine Iaminae. Coarse Iaminations are occasionally graded	Meltwater plume deposits and small-scale pro-glacial debris flows	Ice-marginal glacimarine environment (Ó Cofaigh & Dowdeswell, 2001). GIS and/or IIS are close to/at the core site		

2001). The predominant carbonate (low Fe / Ca) material in this subunit likely originates from northern and/or western Kane Basin.

Faint laminations are visible on the CT scan images of ⁵ subunit 3B (313–305 cm). The sediment of this subunit is composed essentially of clay and silt (47 % and 43 %, respectively) with a relatively low sand content (< 10 % in the <2 mm fraction and each of the coarser fractions represents less than 3 % of the sediment weight). Ti / K ratios have ¹⁰ slightly decreased relative to 3A, but remain high and dis-

play a slightly increasing trend. K counts and Fe / Ca ratios remain low. Analysis of the sieved residues revealed the presence of benthic foraminifera in this subunit, which were picked and dated at ~ 9.4 ¹⁴C BP (9.9 cal ka BP with ¹⁵ $\Delta R = 240$; Table 1).

The poor sorting of sediments in subunit 3B could possibly indicate that they were ice-transported, but the near absence of clasts (e.g. in contrast to the overlaying and underlying subunits of interval 3) contradicts this hypothesis. The ²⁰ modest contribution of clay along with the relatively high silt content rather points to the transport and deposition of these

- sediments by a high-velocity current. The elemental signature of this subunit (low Fe / Ca) denotes a probable northern and/or western Kane Basin origin. Concerning the old
- ²⁵ age yielded from the mixed benthic foraminifera picked in this subunit, the age model shows that these foraminifera were remobilised. It is possible that a small quantity of pre-Holocene foraminifera was mixed in with living fauna. This would imply that sediments predating the last glacia-

³⁰ tion (> 22 cal ka BP) were preserved under the extended GIS and IIS in Nares Strait and were eroded and transported to the core site during the deposition of subunit 3B. An alternative explanation is that the sample is composed of post-glacial specimens of a similar age which were eroded from ³⁵ the seabed and transported to the site.

Subunit 3C (305–300 cm) contains large amounts of coarse material with an average of 44 % sand and only 32 % clay in the <2 mm fraction. The = in this subunit is coarser than in 3A with the 800–125 mum fraction contributing to

- $_{40} \sim 34\%$ of the total sediment, while up to a further 10% of the sediment weight is accounted for by the >800 µm fraction. Ti / K ratios (high) and K counts (low) are similar to subunit 3A, whereas Fe / Ca ratios are high in subunit 3C (Fig. 5).
- ⁴⁵ The very high clast content of subunit 3C along with high Ti / K ratios and the absence of grading are indicative of iceberg rafting and deposition. The shell fragment that was dated in the topmost horizon of this subunit (>42¹⁴C BP) was clearly remobilised, likely by ice rafting. The sedi-
- ⁵⁰ ment forming subunit 3C appears to originate from eastern Kane Basin (Fig. 2) given the high Fe / Ca ratio. The age model points to rapid sedimentation of unit 3 with an age of 8.22 cal ka BP on mixed benthic foraminifera picked from the horizon directly above unit 3, and an age of 8.38 cal ka BP

in a sample 7 cm below the base of unit 3 that extrapolates to ${}_{55} \sim 8.29$ cal ka BP at 320 cm in the age model (Table 1, Fig. 4).

Unit 4 (300–280 cm, 8.3–8.1 cal ka BP) has a similar density and clay content ($\sim 58 \%$) to subunit 2B. The contribution of sand in these sediments, however, is higher than in subunit 2B with $\sim 6.5 \%$ weight accounted for by > 125 µm ⁶⁰ sand and $\sim 14 \%$ sand in the < 2 mm fraction. The elemental composition of unit 4 is also fairly similar to that of subunit 2B. Ti / K ratios are low, while K counts and Fe / Ca ratios are high (Fig. 6).

The high clay content of unit 4 suggests that delivery from 65 meltwater plumes was the dominant sedimentary process at play during this time interval. The substantial amount of sand in this unit indicates that a significant proportion of the sediment was also ice-rafted to the location. As previously mentioned, the increase in ice-rafted debris can indicate (1) in-70 creased calving rates when originating from iceberg rafting, (2) changes in iceberg delivery of sediment (increased melting or dumping of icebergs), or (3) a decrease in the delivery of finer particles that increases the apparent contribution of clasts to the sediment (Hogan et al., 2016, and refer-75 ences therein). The high sedimentation rates ($\sim 90 \,\mathrm{cm}\,\mathrm{ka}^{-1}$ from the age model and $\sim 190 \,\mathrm{cm} \,\mathrm{ka}^{-1}$ from the linear interpolation between the dates at 297.5 cm (8.22 cal ka BP) and 273.5 cm (8.09 cal ka BP); Table 1, Fig. 4) support this narrative of delivery by meltwater and ice rafting that are typically 80 responsible for the transport and deposition of large quantities of sediment (Svendsen et al., 1992; Dowdeswell et al., 1998), while seemingly excluding the possibility of a significant decrease in the delivery of finer particles. High Fe / Ca values suggest that a notable portion of the sediments origi-85 nates from the Precambrian gneisses of eastern Kane Basin, while the slightly decreasing trend displayed by this elemental ratio could potentially be linked to a progressive increase in the contribution of carbonate-rich formations from northern and/or western Kane Basin in this interval.

Unit 5 (280–0 cm, 8.1–0 cal ka BP) clearly differs from underlying units with regard to the <2 mm grain size fraction (Fig. 6). The clay content drops to steady, lower values (49 % on average) and the CT scans show a generally homogenous sediment with frequent traces of bioturbation. Changes in $_{95}$ grain size divide unit 5 into two subunits.

The sediments in subunit 5A (280–250 cm, 8.1– 7.5 cal ka BP) contain a relatively high proportion of sand peaking at 12% in the <2 mm fraction, while the combined contribution of the coarser fractions averages at 100 \sim 5.5% weight. Lonestones occur frequently and are visible in the CT scan images. K counts and Fe / Ca ratios drop sharply to lower values at the base of subunit 5A (Fig. 6). Ti / K is low, but increases very discreetly toward the top of this subunit.

The significant decrease in clay particles in subunit 5A compared to units 4 and 2B suggests that delivery from meltwater plumes was reduced in this interval, either in relation to a decrease in glacial melting rates or to a more ice-distal set-

ting. The scarcity of clasts in this subunit can be explained by a decrease in marine termini of the GIS and/or IIS, a change in the sea ice regime, and/or the counterparts of the aforementioned hypothesis presented in Hogan et al., 2016, i.e.

- $_{5}$ (1) decreased iceberg calving rates or (2) decreased iceberg melting. We rule out hypothesis 3 (i.e. increased contribution of finer particles) given the reduced contribution of finer particles in the <2 mm fraction and the decrease in sedimentation rates from 60 to 40 cm ka⁻¹ in this subunit. The sharp
- ¹⁰ decrease in the Fe / Ca ratio between unit 4 and unit 5 is interpreted as a sudden reduction in the contribution of gneissic material in the sediments of core AMD14-Kane2b.

Subunit 5B (250-0 cm, 7.5-0 cal ka BP) is generally homogenous with lonestones occurring sporadically through-

- ¹⁵ out. The silt content increases gradually from ~ 40 to $\sim 47 \%$ toward the top of the core. The contribution of the coarser fractions to the total sediment weight is fairly stable from the base to ~ 40 cm (1.9 cal ka BP), where the 63–125 µm and > 125 µm fractions account for $\sim 2 \%$ and < 1 % of the to-
- ²⁰ tal sediment weight, respectively. The relative weight of the 63–125 μ m sand fraction doubles to ~4% in the top 40 cm of the core (Fig. 5). Both Fe / Ca and Ti / K ratios increase gradually until ~ 120 cm (~ 4.1 cal ka BP) after which they remain relatively high until the core top.
- A sample of mixed pathic foraminifera yielded a radiocarbon age some 2 kacher than expected at 238.5 cm. This sample probably contains a mixture of coeval and remobilised foraminifera (either by bioturbation or by water–ice transport from another location).
- ³⁰ The overall limited contribution of the coarser fractions to the sediment of subunit 5B in comparison to the underlying lithologic units indicates that ice delivery of sediment was reduced during this interval. Furthermore, the relatively low amounts of clay imply that meltwater delivery
- ³⁵ was also weakened. The sediments of subunit 5B were likely primarily water-transported to the core site (Gilbert, 1983; Hein and Syvitski, 1992). The increase in silt and Ti / K toward the top of the core suggests winnowing by an increase in bottom current (Mulder et al., 2013; Bahr et al., 2014).
- ⁴⁰ Relatively low sedimentation rates $(20-50 \text{ cm ka}^{-1})$ corroborate the narrative that delivery from meltwater plumes was limited in favour of a more hemipelagic sedimentation regime, also supported by the visible bioturbation in this subunit. The increase in fine sand in the most recent sed-
- ⁴⁵ iment may be due to a resumption of ice rafting over the last 1.9 cal ka BP. The gradually increasing trend of Fe / Ca suggests that the contribution of carbonates from northern and/or western Kane Basin diminishes gradually between ~ 270 cm (~ 7.9 cal ka BP) in subunit 5A and ~ 120 cm (\sim
- ⁵⁰ 4.1 cal ka BP) in subunit 5B after which it remains stable until the top of the core.

5 Discussion

Our study of core AMD14-Kane2b has enabled us to reconstruct a succession of depositional environments in Kane Basin following the retreat of the formerly coalescent GIS 55 and IIS in Nares Strait (Fig. 8). Here we discuss our reconstructions in light of other paleoceanographic and paleoclimatic studies to provide a broader view of the Holocene history of Nares Strait (Figs. 6, 7, and 8, Table 2).

Previous studies have shown that the presence of er- 60 ratic Greenland boulders on Ellesmere Island from Kennedy Channel to the northern entrance of Nares Strait attest to the coalescence of the IIS and GIS along the western side of northern Nares Strait during the Last Glacial Maximum (LGM) (e.g. England, 1999). The absence of such erratics 65 along the western and southern coasts of Kane Basin implies that the confluence of the two ice sheets was further at sea in the southern half of the strait (England, 1999). Radiocarbon dating on samples from raised beaches provides minimum ages for marine ingress in Nares Strait. These ages are 70 older in the northern and southern extremities of the strait, while only younger ages are yielded by samples in northern Kane Basin and Kennedy Channel, implying that a central (grounded) ice saddle persevered longer in the shallower sector of the strait (England, 1999, and references therein; 75 Bennike, 2002). In addition to providing minimum ages for ice sheet retreat, ¹⁴C dating on marine-derived material in raised beaches enables one to identify the former shoreline and assess the glacio-isostatic readjustment of the continental crust. However, this approach can only provide minimum 80 ages for (glacial ice-free) aquatic environments at a given place and time and does not necessarily correspond to the position of the ice margin, which can be several kilometres inland. Cosmogenic nuclide surface-exposure dating is an efficient method to temporally constrain inland ice sheet retreat. 85 However, such investigations are scarce in Nares Strait: only two studies document the glacial retreat on Hans Island, off Greenland in Kennedy Channel (Zreda et al., 1999), and in Washington Land (Reusche et al., 2018). England's (1999) paleogeographical maps of ice sheet retreat in Nares Strait 90 based on radiocarbon-dated molluscs were revised in Fig. 8 in which offshore limits for the GIS and IIS are proposed based on our sedimentological and geochemical data from core AMD14-Kane2b. The continuous nature of our record also allows us to propose a more precise chronology of the 95 deglaciation of central Nares Strait.

5.1 Ca. 9.0 cal ka BP: ice sheet retreat in Kane Basin

Our archive demonstrates that marine sedimentation took place in Kane Basin as early as ~ 9.0 cal ka BP. Grain size characteristics and sedimentary structures suggest that the ¹⁰⁰ laminated basal unit (1A) represents the topmost deposits in the ice-marginal environment shortly after ice sheet retreat at the core site (Figs. 5 and 8b, Table 2). The settling




Figure 7. Comparison of sieved grain size data from AMD14-Kane2b and paleoceanographic proxies from HLY03-05CG in Hall Basin (Jennings et al., 2011). Radiocarbon ages presented in Jennings et al. (2011) were calibrated with $\Delta = 240 \pm 51$ (Table S4 in the Supplement) years and the age model for core HLY03-05CG is a linear interpolation between the calibrated ages.

of meltwater plume sediments in the proximal glacial marine environment that followed (1B) is devoid of IRD and seems to have been interrupted by an iceberg-rafted interval (1C). The absence of molluscs predating 8.8 cal ka BP in 5 Kane Basin (England, 1999) likely indicates that following the deglaciation of Smith Sound ca. 9.9 cal ka BP (Fig. 8a–c, England, 1999), ice sheet retreat in Kane Basin occurred off the current coast where melting was potentially enhanced by

the increasing influence of warmer Atlantic water from the ¹⁰ West Greenland Current after 10.9 cal ka BP, $\Delta R = 0$ (Funder, 1990; Kelly et al., 1999; Knudsen et al., 2008). Based on the sedimentary properties of subunit 1A, we propose that ca. 9.0 cal ka BP, the GIS–IIS ice margin was located at the core site, completing the offshore area of England's (1999) pale-¹⁵ ogeographical map for this period (Fig. 8b). The IRD-rich unit 1C, which appears to have been deposited by intense ice calving, could potentially mark the opening of Kennedy Channel. Our age of ~ 9.0 cal ka BP for this unit agrees relatively well with the inferred age of an IRD-rich unit in a ²⁰ sediment core from Hall Basin that was interpreted as the opening of Kennedy Channel at ~ 8.6 cal ka BP ($\Delta R = 240$) (Jennings et al., 2011). Alternatively, unit 1C could have been deposited during a readvance of the IIS-GIS in Kane Basin in relation to a cold event. Laurentide ice sheet readvances have been documented through the dating of end and lateral 25 moraines on Baffin Island aged between 9 and 8 cal ka BP (Andrews and Ives, 1978) and have been linked to colder periods. A particularly cold event ca. 9.2-9.3 cal ka BP, which is reported in the regional literature from ice core (Vinther et al., 2006; Fisher et al., 2011) and lacustrine records (Ax- 30 ford et al., 2009), may be the source of the calving event in Kane Basin that led to the deposition of unit 1C. Reservoir ages in Kane Basin are likely to have been reduced prior to the collapse of the IIS-GIS ice saddle in Kennedy Channel and the arrival of poorly ventilated Arctic water. The age 35 of unit 1 with $\Delta R = 0$ is 9.3 cal ka BP, which suggests to us that subunit 1C could well have been deposited during the 9.2–9.3 cal ka BP cold event.

5.2 9.0–8.3 cal ka BP: ice-proximal to ice-distal environment in Kane Basin

The increasingly finer particles that compose unit 2 suggest a growing distance between the core site and the ice margin. The dominant sedimentary process at play is settling




Figure 8. GIS and IIS retreat in Nares Strait. Adapted from England (1999) and including data from Bennike (2002) for Washington Land. Locations for core AMD14-Kane2b in Kane Basin and HLY03-05 (Jennings et al., 2011) in Hall Basin are marked by crosses. All mollusc ages from England (1999) were calibrated with $\Delta R = 240$ using Calib 7.1 (Stuiver et al., 2018) after first adding 410 years to the calibrated ages presented in England (1999) (Table S2 and Fig. S3 in the Supplement). The position of the GIS and IIS margins offshore in Kane Basin are deduced from our sedimentological and geochemical data, while their locations in Hall Basin are deduced from the data presented in Jennings et al. (2011) and Jakobsson et al. (2018).

from meltwater plumes, which is typically responsible for high sedimentation rates, along with frequent delivery of IRD (Table 2). The Early Holocene was characterised by high atmospheric temperatures during the Holocene Thermal Maxi-5 mum (HTM) occasioned by greater solar insolation (Bradley,

- 1990). The HTM has been defined for the eastern sector of the CAA as the period between 10.7 and 7.8 cal ka BP based on the Agassiz ice core record (Lecavalier et al., 2017). The high melting rates of the ice sheets during the HTM (Fisher
- ¹⁰ et al., 2011) likely enhanced the delivery of particles by meltwater and contributed to the high sedimentation rates observed in our core. More distant glacial ice from the site is also in good agreement with the occurrence of molluscs dated between 8.8 and 8.4 cal ka BP on Ellesmere Island and

Northwest Greenland (Fig. 8c, England et al., 291516). The elemental signature of subunit 2B may suggest, however, that the GIS was still present in eastern Kane Basin and delivered material derived from the gneiss basement to the core site. The volcanic clastics on Ellesmere Island may have also contributed to Fe counts in our geochemical record, but we consider their input marginal given the limited surface of this geological unit compared to the gneiss and crystalline basement, which outcrops in much of Inglefield Land and underlays Humboldt Glacier (Dawes and Garde, 1517 2 4). Furthermore, the IIS was a cold-base ice sheet (e.g. Tushingham, 1990; Dyke et al. 1518, 2) and as such likely delivered overall less sediment from meltwater than the warm-based GIS. The occurrence of IRD in unit 2 may imply that relatively open water conditions occurred during this interval, enabling icebergs to drift in Kane Basin, although this may simply be a consequence of high calving rates as the GIS and IIS retreat. Reduced sea ice occurrence in Kane Basin during

- ⁵ the Early Holocene would be in good agreement with low sea ice concentrations reported nearby in Lancaster Sound (from 10 to 6 cal ka BP, $\Delta R = 290$, Vare et al., 2009; from ~ 10– 7.8 cal ka BP, R = 335, Pienkowski et al., 2012). However, while the decreasing trend of the coarse fraction in unit 2 may
- ¹⁰ indicate more stable sea ice conditions (or decreasing calving rates) toward the end of the interval, fluctuations in the coarse fractions in our record may also suggest that sea ice conditions were variable. This is in line with both decreasing atmospheric temperatures towards the end of the HTM
- ¹⁵ (Lecavalier et al., 2017) and the Knudsen et al. (2008) observations of variable West Greenland Current influence and sea ice conditions between 9.5 and 8.2 cal ka BP in northernmost Baffin Bay.

5.3 8.3 cal ka BP: the opening of Kennedy Channel

- ²⁰ Unit 3 appears to be primarily iceberg-rafted, with an inclusion of a finer, water-transported silty subunit (3B). A foraminifera-derived radiocarbon age obtained from subunit 3B (Table 1) suggests sediment remobilisation within this time interval. If we consider unit 3A to have been deposited
- ²⁵ by the passing over Kane Basin of glacial ice having broken up in Kennedy Channel, then a plausible origin for unit 3B could be the entrainment of sediment from northern Nares Strait associated with the discharge of large amounts of water as the connection was established. The absence of any
- ³⁰ molluscs in Kennedy Channel predating 8.1 cal ka BP further suggests that Kennedy Channel was still blocked until then, although this method can only provide minimum ages for ice sheet retreat (Fig. 8e–g). This proposed age for the opening of Kennedy Channel is only slightly younger than
- ³⁵ that proposed by Jennings et al. (2011), i.e. ~ 8.6 cal ka BP ($\Delta R = 240$, Fig. 7), based on the estimated age of an IRD event in Hall Basin, northern Nares Strait (core HLY03-05GC). Both ages can be reconciled assuming that bottom waters in Hall Basin were probably poorly ventilated be-
- ⁴⁰ fore the opening of the strait, inducing a higher reservoir age in the northern sector of Nares Strait. Furthermore, one might consider the possibility that the transitional IRD-rich unit in core HLY03-05GC that is interpreted by Jennings et al. (2011) as representing the opening of Kennedy Channel
- ⁴⁵ might in fact represent instabilities in the GIS–IIS prior to – and eventually leading to – the complete opening of the strait. If so, the transition from laminated to bioturbated mud in the Hall Basin sediment record which, according to Xradiography, CT scans, and the age model of core HLY03-
- ⁵⁰ 05GC, occurred close to 8.5 cal ka BP, ie. ca. 100 years after the deposition of the IRD-rich unit (Jennings et al., 2011), might in fact represent the true opening of Nares Strait (i.e. change from a rather confined Hall Basin to a ventilated envi-

ronment under the influence of a strong southward current). Finally, we assume that the collapse of glacial ice in Kennedy 55 Channel was more likely to have been recorded as an IRDrich interval south of the channel (i.e. Kane Basin) in the direction of the presumable southward flow, rather than to the north.

It has recently been demonstrated that the Humboldt 60 Glacier retreated from a previous position of stability ca. 8.3 ± 1.7 ka BP based on surface-exposure dating of an abandoned lateral moraine in Washington Land (Reusche et al., 2018). This instability in the Humboldt Glacier may have been linked to the break-up of glacial ice in Kennedy Channel. Furthermore, the onset of decreasing landfast sea ice on the northern coast of Ellesmere Island and northern Greenland after 8.2 cal ka BP (England et al., 2008; Funder et al., 2011) may have been associated with the flushing of ice through Nares Strait after the opening of Kennedy Chan-70 nel. The local temperature drop recorded in the Agassiz ice core (Lecavalier et al., 2017) and, as suggested by Reusche et al. (2018), in Baffin Bay lacustrine records (Axford et al., 2009) may have been associated with oceanographic and atmospheric reorganisation resulting from the opening 75 of Kennedy Channel, as well as the "8.2 event". Given the excellent correspondence between the aforementioned evidence, we consider subunits 3A and 3B to have been deposited as the ice saddle in Kennedy Channel broke up. The high carbonate signal in the elemental data (Fig. 6) also sug- 80 gests that the sediments from subunits 3A and 3B originated from northern Nares Strait (Fig. 2) rather than the Humboldt Glacier alone.

The dominant depositional process in subunit 3C is iceberg rafting based on the abundance of clasts in this interval. The elemental composition of subunit 3C suggests that the sedimentary material likely originates from the GIS in eastern Kane Basin (Fig. 2). Investigations into the internal stratigraphy of the GIS and their comparison to north Greenland ice cores have demonstrated that the collapse of the ice saddle in Kennedy Channel triggered the acceleration of glacial fluxes along Nares Strait (MacGregor et al., 2016). The destabilisation of the GIS following the collapse of the ice saddle may have provoked intense calving that led to the deposition of subunit 3C. In this regard, intense calving of the Humboldt Glacier as recently dated by Reusche et al. (2018) at 8.3 ± 1.7 ka BP might explain the observed elemental signature of the top part of unit 3.

However, the Reusche et al. (2018) findings also offer an alternative scenario for the deposition of unit 3. Intense ¹⁰⁰ calving of the Humboldt Glacier may have occurred as it retreated in eastern Kane Basin and abandoned a lateral moraine in Washington Land ca. 8.3 ± 1.7 ka BP (Reusche et al., 2018). This alternative scenario alludes to the possibility that the opening of Kennedy Channel may rather have ¹⁰⁵ occurred ca. 9.0 cal ka BP (unit 1C). The elemental signature of subunit 3A and 3B does not, however, point to an eastern source and rather supports a northern-western origin of these sediments.

5.4 8.3–8.1 cal ka BP: increased iceberg delivery to Kane Basin

- ⁵ The abundance of iceberg-rafted debris has increased considerably in unit 4 compared to unit 2. This is possibly the result of the aforementioned acceleration of the GIS and IIS along Nares Strait following the collapse of the ice saddle in Kennedy Channel (MacGregor et al., 2016), as well as the ¹⁰ arrival of icebergs from new sources to Kane Basin situated in northern Nares Strait. The retreating GIS in eastern Kane Basin was likely a primary source of icebergs during this period. However, the high clay content in our record implies that the GIS was still relatively close to the core site and had ¹⁵ not yet fully retreated in eastern Kane Basin, contributing to
- the high sedimentation rates recorded in this unit (Fig. 8e).

5.5 8.1–7.5 cal ka BP: rapid retreat of the GIS in Kane Basin

The abrupt decrease in clay content and sedimentation rates ²⁰ at 280 cm in our record implies that the ice margin abruptly retreated ca. 8.1 cal ka BP (Fig.6, Fig. 8f). The equal drop in Fe / Ca ratios suggests that it was probably the GIS that retreated rapidly in eastern Kane Basin. This abrupt retreat may have been initiated by the removal of the glacial but-25 tress in Kennedy Channel (unit 3). The subsequent decrease in the >125 μ m fraction may be associated with the onset of the deceleration of glacial fluxes along Nares Strait, as well as more distant glacial ice in eastern Kane Basin resulting from the retreat of the GIS. The timing of the retreat of 30 the GIS in eastern Kane Basin corresponds remarkably well with the aforementioned abandonment of a lateral moraine by the Humboldt Glacier (Reusche et al., 2018). The authors in this recent study warn that two samples may be contaminated by previous exposure and that the age of abandon-35 ment of the moraine is likely to be younger than the pro-

- posed 8.3 ± 1.7 ka BP. Given the uncertainties in our radiocarbon dataset (analytical errors and ΔR uncertainties) and in the Reusche et al. (2018) surface-exposure dataset, both our dating of the opening of Kennedy Channel and the retreat
- ⁴⁰ of Humboldt Glacier are within the uncertainty range of the dating of the abandonment of the moraine by the Humboldt Glacier. It is thus difficult to distinguish whether this event was linked to the deglaciation of Kennedy Channel at \sim 8.3 cal ka BP or whether it was delayed until \sim 8.1 cal ka BP
- ⁴⁵ after the cold "8.2 event" that may have brought a short period of stability to the GIS.

5.6 7.5-0 cal ka BP: deglaciation of Washington Land

The low Fe / Ca ratios at the beginning of this interval are likely related to the erosion and delivery of material from

Washington Land and a decrease in the delivery of crys- 50 talline material by the GIS (Fig. 6). The progressive increase in Fe/Ca between 7.5 and 4.1 calkaBP can be linked to the deglaciation of Washington Land. The oldest molluscs found on the southern coast of Washington Land are dated between 7.8 and 7.5 calka BP, while specimens found in 55 morainic deposits imply that the extent of the GIS reached a minimum between 4 and 0.7 cal ka BP (Fig. 7, Bennike, 2002). The decrease in the coarser fractions in our core after ca. 7.5 cal ka BP may be the result of reduced marine termini of the GIS and hence less calving as the Green- 60 land coast became deglaciated (Fig. 8g, Bennike, 2002). Increasing silt and Ti / K in our core suggest winnowing by stronger bottom water currents. We propose that as the glacio-isostatic rebound lifted the continental crust in Nares Strait, the seabed was progressively brought closer to the 65 stronger subsurface currents. The isostatic rebound in Kane Basin has been estimated to be between 80 and 120 m (England, 1999, and references therein), which would have had considerable consequences on bottom water velocities. Interestingly, increased sedimentation rates in Kane Basin be-70 tween \sim 4.5 and 2.8 cal ka BP (Fig. 3) coincide with a period of atmospheric warming recorded in the Agassiz ice core (Lecavalier et al., 2017). These higher sedimentation rates may have been associated with increased delivery of sediment by meltwater from the GIS and the residual ice caps on 75 Ellesmere Island during a warmer period. The increase in the contribution of the coarse fraction in core AMD14-Kane2B over the last 1.9 kyr is suggestive of minimal seasonal sea ice and/or higher calving rates over the last 2 millennia in Kane Basin. This broadly coincides with low absolute di- 80 atom abundances in northernmost Baffin Bay, attesting to poor productivity rates after 2.0 cal ka BP; $\Delta R = 0$ (Knudsen et al., 2008). The "bridge dipole" between Kane Basin and northernmost Baffin Bay entails the following: when sea ice conditions in Kane Basin are strong, surface conditions to the south of Smith Sound are largely open with the NOW Polynya being productive and vice versa (Barber et al., 2001). This inverse relationship between sea ice conditions in Kane Basin and northernmost Baffin Bay has probably been true for at least the past ca. 2 kyr. Recent insta- 90 bilities in the ice arch in Kane Basin that have led to increased sea ice export towards northernmost Baffin Bay have been observed by satellite imagery and hence are only documented for the past few decades. Together with the Knudsen et al. (2008) study in northern Baffin Bay, our results 95 suggest that these instabilities may have begun as early as ca. 2 cal ka BP. Late Holocene decreases in sea ice occurrence, indicative of milder conditions, were also documented in other sectors of the CAA such as in Barrow Strait between 2.0 and 1.5 cal ka BP (Pienkowski et al., 2012) or in the adja-100 cent Lancaster Sound between 1.2 and 0.8 cal ka BP (Vare et al., 2009).

6 Conclusion

Our investigation of core AMD14-Kane2b has provided, for the first time, a paleo-environmental reconstruction in Kane Basin over the last ca. 9.0 kyr. The confrontation of our

- ⁵ dataset with both land-based (England, 1999; Bennike, 2002, Reusche et al., 2018) and marine (Jennings et al., 2011) evidence offers several alternative paleo-environmental interpretations for our record. Of particular interest is the determination of which of the two IRD-rich units (unit 1c
- $_{10} \sim 9.0$ cal ka BP or unit 3 ~ 8.3 cal ka BP) in core AMD14-Kane2b might represent the opening of Kennedy Channel. We consider the evidence to be in favour of a later collapse of glacial ice in Kennedy Channel ca. 8.3 cal ka BP that may have been linked to instabilities in the Humboldt Glacier
- ¹⁵ ca. 8.3–8.1 cal ka BP (Reusche et al., 2018). Our findings concerning the successive paleo-environments in this central sector of Nares Strait following ice sheet retreat can be summarised as follows.


While evolving from a short-lived ice-proximal deposi-²⁰ tional environment at ~ 9.0 cal ka BP to a rather secluded and narrow bay as the ice sheets retreated, compelling evidence indicates that Kane Basin was not connected to Hall Basin until the collapse of the GIS–IIS saddle in Kennedy Channel at ~ 8.3 cal ka BP. The collapse of the glacial but-

- ²⁵ tress in Kennedy Channel may have triggered the acceleration of glacial fluxes toward Nares Strait, increasing calving and iceberg-rafted debris in Kane Basin between 8.3 and 7.5 cal ka BP. Instabilities in the GIS eventually resulted in the rapid retreat of glacial ice from eastern Kane Basin at
- ³⁰ 8.1 cal ka BP. As the basin underwent shoaling induced by the glacio-isostatic rebound, the retreat of the GIS in Washington Land gradually reduced inputs of carbonate materiel to Kane Basin. A possible deterioration in sea ice conditions and/or increased iceberg release appear to have taken place ³⁵ over the last ca. 2 kyr and correspond with lower sea ice oc-

currence in other sectors of the CAA.

This archive provides a new viewpoint that has enabled us to propose a continuous timeline of the events related to the deglaciation of Kane Basin, which until now relied 40 entirely on land-based studies. Our study suggests that the "bridge dipole" presented in Barber et al. (2001), in which warmer (colder) years exhibit more (less) sea ice in Smith

Sound and less (more) ice in Nares Strait, may be extrapolated over the last 2 millennia. Future investigations into ⁴⁵ the Holocene variability of sea ice conditions in Kane Basin may provide a more comprehensive view on its controlling effect on the NOW Polynya. High productivity rates in the NOW Polynya, however, are also fuelled by the throughflow of nutrient-rich Pacific water via Nares Strait, and further ⁵⁰ investigation into how oceanographic circulation responded to postglacial changes in Nares Strait will provide more insight into the Holocene evolution of this highly productive area of the Arctic. Other than emphasising the need for further research into local reservoir age corrections, our study is inclined to contribute to future work on the export of lowsalinity Arctic water and Holocene variations of deep water formation (Hoogakker et al., 2014; Moffa-Sanchez and Hall, 2017).



Acknowledgements. Eleanor Georgiadis' studentship is funded ⁶⁵ by both the Initiative d'Excellence (IdEx) programme of the University of Bordeaux and the Natural Science and Engineering Research Council of Canada (NSERC). We would like to thank Anne Jennings, Sofia Ribeiro, Audrey Limoges, and Karen Luise Knudsen for constructive conversations on the history of the North ⁷⁰ Water Polynya and Benoit Lecavalier for having share thus the much appreciated Agassiz ice core temperature record this work is supported by the Fondation Total, the French Agence Nationale de la Recherche (GreenEdge project), the Network of Centres of Excellence ArcticNet, and the European Research Council (StG IceProxy). Finally, we wish to thank the CCGS *Amundsen* captain, officers, and crew for their support during the 2014 ArcticNet cruise.

Edited by: Ed Brook Reviewed by: two anonymous referees

References

- Andrews, J., T. and Ives, J. D.: "Cockburn" Nomenclature and the Late Quaternary History of the Eastern Canadian Arctic, Arctic Alpine Res., 10, 617–633, 1978.
- Albertson, M. L., Dai, Y. B., Jensen, R. A., and Rouse, H.: Diffusion of submerged jets, T. Am. Soc. Civ. Eng., 115, 639–664, 1950.
- Axford, Y., Briner, J. P., Miller, G. H., and Francis, D. R.: Paleoecological evidence for abrupt cold reversals during peak Holocene warmth on Baffin Island, Arctic Canada, Quaternary Sci. Rev., 71, 142-149, 2009.
- Bahr, A., Jimenez-Espejo, F. J., Kolasinac, N., Grunert, P., Hernández-Molina, F. J., Rohl, U., Voelker, A. H. L., Escutia, C., Stow, D. A. V., Hodell, D., and Alvarez- ⁹⁵ Zarikian, C. A.: Deciphering bottom current velocity and paleoclimate signals from contourite deposits in the Gulf of Cádiz during the last 140 kyr: An inorganic geochem-

ical approach, Geochem. Geophy. Geosys., 15, 3145–3160, https://doi.org/10.1002/2014GC005356, 2014.

- Bailey, W. B.: Oceanographic Features of the Canadian Archipelago, J. of the Fish. Res. Board Can., 14, 57523, 1957.
- Barber, D. G., Hanesiak, J. M., Chan, W., and Piwowar, J.: Sea-ice and meteorological conditions in Northern Baffin Bay and the North Water polynya between 1979 and 1996, Atmos. Ocean, 39, 343–359, 2001.
- ¹⁰ Belkin, I. M., Levitus, S. Antonov, J., and Malmberg, S. A.: "Great Salinity Anomalies" in the North Atlantic, Prog. Oceanogr. 41, 1–68, 1998.
- Bennike, O.: Late Quaternary history of Washington Land, North Greenland, Boreas, 31, 260–272, 2002.
- ¹⁵ Bennike, O., Dawes, P. R., Funder, S., Kelly, M., and Weidick, A.: The late Quaternary history of Hall Land, Northwest Greenland: Discussion, Can. J. Earth Sci., 24, 370–374, 1987.
- Bervid, H., Carlson, A., Hendy, I., Walczak, M., Stoner, J.: Deglacial sea-surface temperature change and rapid response
- along the western margin of the northern and southern Cordilleran ice sheet, Geological Society of America, Abstracts with Programs, 49, 6, https://doi.org/10.1130/abs/2017AM-306898, 2017.
- Blaauw, M.: Methods and code for "classical" age-modelling of ra-
- diocarbon sequences, Quat. Geochronol., 5, 512–518, 2010.
 Blake Jr., W.: Age determination on marine and terrestrial materials
- of Holocene age, southern Ellesmere Island, Arctic Archipelago, Geol. Surv. Can., 79, 105–109, 1979.
- Blake Jr., W., Boucherle, M. M., Fredskild, B., Jannssens, J. A.,
- and Smol, J. P.: The geomorphological setting, glacial history and Holocene development of "Kap Inglefield Sø", Inglefield Land, North-West Greenland. Meddelelser om Grønland, Geosci., 27, IS24 1992.
- Blake Jr., W., Jackson, H. R., and Currie, C. G.: Seafloor evidence
- for glaciation, northernmost Baffin Bay, B. Geol. Soc. Denmark, 43, 157–168, 1996.
- Bradley, R. S.: Holocene paleoclimatology of the Queen Elizabeth islands, Canadian high arctic, QRS, 9, 365–384, https://doi.org/10.1016/0277-3791(90)90028-9, 1990.
- ⁴⁰ Briner, J. P., Nicholas, P., McKay, N. P., Axford, Y., Bennike, O., Bradley, R. S., de Vernal, A., Fisher, D., Francus, P., Fréchette, B., Gajewski, K., Jennings, A., Kaufman, D. A., Miller, G., Rouston, C., and Wagner, B.: Holocene climate change in Arctic Canada and Greenland, Quaternary Sci. Rev., 15251-2 - 16.
- 45 Caron, M., Montero-Serrano, J.-C., St-Onge, G., Rochon, A., Giraudeau, J., and Massé, G.: Holocene sediment dynamics on the north-western Greenland glaciated margin: insight from sedimentological, mineralogical, and magnetic data, in preparation [1526], 2018.
- ⁵⁰ Christie, R. L.: Geological reconnaissance of northeastern Ellesmere Island, district of Franklin, Geol. Surv. Can., 33 27 1964.
- Christie, R. L.: Northeastern Ellesmere Island: Lake Hazen region and Judge Daly Promontory structural geology, stratigraphy and
- ⁵⁵ palaeontology, Geol. Surv. Can. Report of Activities, 74-1, 297– 299, 1973.
- Coulthard, R. D., Furze, M. F. A., Pienkowski, A. J., Nixon, F. C., and England, J. H.: New marine DR val-

ues for Arctic Canada, Quat. Geochronol., 5, 419–434, https://doi.org/10.1016/j.quageo.2010.03.002, 2010.

60

- Davies, H. C., Dobson, M. R., and Whittington, R. J.: A revised seismic stratigraphy for Quaternary deposits on the inner continental shelf of Scotland between 55°30′ N and 57°30′ N, Boreas, 13, 49–66, 1984.
- Dawes, P. R.: Precambrian to Tertiary of northern Greenland, in: 65 Geology of Greenland, edited have Escher, A. and Watt, W. S., Geol. Surv. Greenland, 1528248 - 1, 1976.
- Dawes, P. R. and Garde, A. A.: Geological map of Greenland, 1:500 000, Humboldt Gletscherenheet 6. Copenhagen, Geol. Surv. Den. Greenl., [1529] 2004.
- Dowdeswell, J. A., Uenzelmann-Neben, G., Whittington, R. J., and Marienfeld, P.: The Late Quaternary sedimentary and in Scoresby Sund, East Greenland, Boreas, 23, 294–310, 1
- Dowdeswell, J. A., Elverhøi, A., and Spielhagen, R.: Glacimarine sedimentary processes and facies on the polar north Atlantic margins, QRS, 17, 243–272, 1998.
- Dowdeswell, J. A., Whittington, R. J., Jennings, A. E., Andrews, J. T., Mackensen, A., and Marienfeld, P.: An origin for laminated glacimarine sediments through sea-ice build-up and sup ed iceberg rafting, Sedimentology 47, 557–576, 2000.
- Dyke, A. S., Hooper, J. M. G., and Savelle, J. M.: A history of sea ice in the Canadian Arctic Archipelago based on postglacial remains of the bowhead whale (Balaena mysticetus), Arctic, 49, 235–255, 1996.
- Dyke, A. S., Andrews, J. T., Clark, P. U., England, J. H., Miller, G. ⁸⁵ H., Shaw, J., and Veillette, J. J.: The Laurentide and Innuitian ice sheets during the last glacial maximum, Quaternary Sci. Rev., 21, 9–31, 2002.
- Elverhøi, A., Liestel, O., and Nagy, J.: Glacial erosion, sedimentation and microfauna in the inner part of Kongsfjorden, Spitsbergen, Norsk Polarinst. Skri., 172, 33–58, 1980.
- England, J.: Coalescent Greenland and Innuitian ice during the Last Glacial Maximum: Revising the Quaternary of the Canadian High Arctic, Quaternary Sci. Rev., 18, 421–426, https://doi.org/10.1016/S0277-3791(98)00070-5, 1999.
- England, J., Dyke, A. S., Coulthard, R. D., McNeely, R. and Aitken, A.: The exaggerated radiocarbon age of deposit-feeding molluscs in calcareous environments, Boreas, 42, 362–373, https://doi.org/10.1111/j.1502-3885.2012.00256.x, 2013.
- England, J. H. K., Lakeman, T. R., Lemmen, D. S., Bednarski, ¹⁰⁰ J. M., Stewart, T. G., and Evans, D. J. A.: A millennial-scale record of Arctic Ocean sea ice variability and the demise of the Ellesmere Island ice shelves, Geoph. Res. Lett., 35,**11533** https://doi.org/10.1029/2008GL034470, 2008.
- Fisher, D., Zheng, J., Burgess, D., Zdanowicz, C., Kin- ¹⁰⁵ nard, C., Sharp, M., and Bourgeois, J.: Recent melt rates of Canadian Arctic ice caps are the highest in four millennia, Global Planet. Change, 84–85, 3–7, https://doi.org/10.1016/j.gloplacha.2011.06.005, 2011.
- Funder, S.: Late Quaternary stratigraphy and glaciology in the 110 Thule area, Northwest Greenland, Meddelelser om Grønland, Geosci., 22, 1–63, 1990.
- Funder, S., Goosse, H., Jepsen, H., Kaas, E., Kjær, K. H., Korsgaard, N. J., Larsen, N. K., Linderson, H., Lyså, A., Möller, P., Olsen, J., and Willerslev, E.: A 10000-Year Record of Arctic ¹¹⁵ Ocean Sea-Ice Variability – View from the Beach, Science, 333, 747–750, 2011.

- Gilbert, R.: Sedimentary processes of Canadian Arctic fjords, Sediment. Geol., 36, 147–175, 1983.
- Guyard, H., Chaprin, E., St-Onge, G., and Labrie, J.: Late-Holocene NAO and oceanic forcing on high-altitude proglacial sedimenta-
- tion (Lake Bramant, Western French Alps), The Holocene, 23, 1163–1172, 2013.
- Harrison, J. C., Brent, T. A., and Oakey, G. N.: Bedrock Geology of the Nares Strait Region of Arctic Canada and Greenland, with explanatory text and GIS content, Geol. Surv. Can., Open File
 5278, 74, 185–189, 2006.
- Harrison, J. C., St-Onge, M. R., Petrov, O. V., Strelnikov, S. I., Lopatin, B. G., Wilson, F. H., Tella, S., Paul, D., Lynds, T., Shokalsky, A. P., Hults, C. K., Bergman, S., Jepsen, H. F., and Solli, A.: Geological map of the Arctic, Geol. Surv. Can., Map
 ⁵ 2159A, scale 1:5000000, 2011.
- Hein, F. J. and Syvitski, J. P. M.: Sedimentary environments and facies in an Arctic basin, Itirbilung Fiord, Baffin Island, Canada. Sediment. Geol., 81, 17–45, 1992.

Hogan, K., Ó Cofaigh, C., Jennings, A., Dowdeswell, J., and Hiem-

- stra, J.: Deglaciation of a major palaeo-ice stream in Disko Trough, West Greenland, Quaternary Sci. Rev., 147, 5–26, 2016.
- Hoogakker, B. A. A., McCave, I. N., Elderfield, H., Hillaire-Marcel, C., and Simstich, J.: Holocene climate variability in the Labrador Sea, J. Geol. Soc. London, 172, 272–277, https://doi.org/10.1144/jgs2013-097, 2014.
- Jakobsson, M., Hogan, K. A., Mayer, L. A., Mix, A., Jennings, J., Stoner, J., Eriksson, B., Jerram, K., Mohammad, R., Pearce, C., Reilly, B., and Stranne, C.: The Holocene retreat dynamics and stability of Petermann Glacier in northwest Greenland, Nat.
 ³⁰ Commun. 9, 1534 dc = 1/10.1038/s41467-018-04573-2, 2018.
- Jennings, A. E., Sheldon, C., Cronin, T. M., Francus, P., Stoner, J., and Andrews, J. T.: The Holocene history of Nares Strait: transition from glacial bay to Arctic-Atlantic throughflow, Oceanography, 24, 26–41, 2011.
- ³⁵ Jones, E. P. and Eert, A. J.: Waters of Nares Strait in 2001 (printed 2006), Polarforschung, 74, 185–189, 2004.
- Jones, E. P., Swift, J. H., Anderson, L. G., Lipizer, M., Civitarese, G., Falkner, K. K., Kattner, G., and McLaughlin, F.: Tracing Pacific water in the North Atlantic Ocean, J. Geophys. Res., 108, 3116, https://doi.org/10.1029/2001JC001141, 2003.
- Kalkreuth, W. D., McCullough, K. M., and Richardson, R. J. H.: Geological, Archaeological, and Historical Occurrences of Coal, East-central Ellesmere Island, Arctic Canada, Arctic Alpine Res., 25, 277–307, 1993.
- ⁴⁵ Kelly, M. and Bennike, O.: Quaternary Geology of Western and Central North Greenland, Rapport Grønlands Geologiske Undersøgelse 153, 341535, 1992.
 - Kelly, M., Funder, S., Houmark-Melsen, M., Knudsen, K. L., Kronborg, C., Landvik, J., and Sorby, L.: Quaternary glacial and ma-
- ⁵⁰ rine environmental history of Northwest Greenland: a review and reappraisal, Quaternary Sci. Rev., 18, 373–392, 1999.
- Kerr, J. W.: Stratigraphy of Central and Eastern Ellesmere Island, Arctic Canada, Part I, Protectic and Cambrian, Geol. Surv. Can., 15366 71537, Part 7067.
- 55 Kerr, J. W.: Stratigraphy of Central and Eastern Ellesmere Islan Arctic Canada, Part II, Ordovician, Geol. Surv. Can., 15386 271539, EI, 1968.

- Kliem, N. and Greenberg, D. A.: Diagnostic simulations of the summer circulation in the Canadian Arctic Archipelago, Atmos. Ocean., 41, 273–289, https://doi.org/10.3137/ao.410402, 2003.
- Knudsen, K. L., Stabell, B., Seidenkrantz, M.-S., Eiriksson, J., and Blake Jr., W.: Deglacial and Holocene conditions in northernmost Baffin Bay: sediments, foraminifera, diatoms and stable isotopes, Boreas, 37, 346–376, https://doi.org/10.1111/j.1502-3885.2008.00035.x, 2008.
- Koch, L.: Stratigraphy of Greenland, Meddr. Grønland, 73, 205–320, 1929a.
- Koch, L.: The Geology of the South Coast of Washington Land, Meddr. Grønland, 73, 205–320, 1929b.
- Koch, L.: The geology of Inglefield Land, Meddr. Grønland, 73, 70 38
- Kravitz, J. H.: Textural and Mineralogical Characteristics of the Surficial Sediments of Kane Basin, J. Sedimetary Petrology., 46, 710–725, 1976.
- Kravitz, J. H.: Sediments and sediment processes in Kane Basin, a ⁷⁵ high Arctic glacial marine basin. University of Colorado, Institute of Arctic Alpine Res., Occasional Paper, 39, 1541 198
- Lecavalier, B. S., Fisher, D. A., Milne, G. A., Vinther, B. M., Tarasov, L., Huybrechts, P., Lacelle, D., Main, B., Zheng, J., Bourgeois, J., and Dyke, A. S.: High Arctic Holocene temperature record from the Agassiz ice cap and Greenland ice sheet evolution, P. Natl. Acad. Sci. USA, 114, 5952–5957, https://doi.org/10.1073/pnas.1616287114, 2017.
- Levac, E., de Vernal, A., and Blake Jr., W.: Sea-surface conditions in the northernmost Baffin Bay during the Holocene: Palynological ⁸⁵ evidence, J. Quaternary Sci., 16, 353–363, 2001.
- List, E. J.: Turbulent jets and plumes, Annu. Rev. Fluid Mech., 14, 189–212, 1982.
- MacGregor, J. A., Colgan, W. T., Rahnestock, M. A., Morlighem, M., Catania, G. A., Paden, G. A., and Gogineni, S. P.: Holocene deceleration of the Greenland Ice Sheet, Science, 351, 6273, 590–593, https://doi.org/10.1126/science.aab1702, 2016.
- McGeehan, T. and W. Maslowski,: Evaluation and control mechanisms of volume and freshwater export through the Canadian Arctic Archipelago in a high-resolution pan- ⁹⁵ Arctic ice ocean model, J. Geophys. Res., 117, C00D14, https://doi.org/10.1029/2011JC007261, 2012.
- McNeely, R., Dyke, A. S., and Southon, J. R.: Marine Reservoir Ages Preliminary Data Assessment, Geol. Surv. Can. Open File 5049, 2006.
- Melling, H., Gratton, Y., and Ingram, R. G.: Ocean circulation within the North Water polynya of Baffin Bay. Atmos. Ocean 9, 301–325, https://doi.org/10.1080/07055900.2001.9649683, 2001.
- Miall, A. D.: Tertiary sedimentation and tectonics in the Judge Daly 105 Basin, northeast Ellesmere Island, Arctic Canada, Geol. Surv. Can., 15428 = 1543, = .
- Moffa-Sanchez, P. and Hall, I. R.: North Atlantic variability and its links to European climate over the last 3000 years, Nat. Commun., 1726, IISIA 2 =
- Møller, H. S., Jensen, K. G., Kuijpers, A., Aagaard-Sørensen, S., Seidenkrantz, M.-S., Prins, M., Endler R., and Mikkelsen, N.: Late-Holocene environment and climatic changes in Ameralik Fjord, southwest Greenland: evidence from the sedimentary record, The Holocene, 61, 685–695, 115 https://doi.org/10.1191/0959683606hl963rp, 2006.

note the remarks at the end of the manuscript

60

65

100

- Moynihan, M. J.: Oceanographic observations in Kane Basin, September 1968 and July–September 1969, United States Coast Guard Oceanographic Report 55, 70, 1972.
- Mudie, P. T., Rochon, A., Prins, M. A., Soenarjo, D., Troelstra,
- S. R., Levac, E., Scott, D. B., Roncaglia, L., and Kuijpers, A.: Late Pleistocene–Holocene marine geology of Nares Strait region: Palaeoceanography from foraminifera and dinoflagellate cysts, sedimentology and stable isotopes (printed 2006), Polarforschung, 74, 169–183, 2004.
- ¹⁰ Muench, R. D.: Oceanographic conditions at a fixed location in western Kane Basin, May 1969, Oceanogr. Rep. CG 373-44, 1–5, U.S. Coast Guard, Washington, D.C., USA, 1971.
- Mulder, T., Hassan, R., Ducassou, E., Zaragosi, S., Gonthier, E., Hanquiez, V., Marchès, E., and Toucanne, S.: Contourites in the
- ⁵ Gulf of Càdiz: A cautionary note on potentially ambiguous indicators of bottom current velocity, Geo-Mar. Lett., 33, 357–367, https://doi.org/10.1007/s00367-013-0332-4, 2013.
- Münchow, A.: Volume and freshwater flux observations from Nares Strait to the west of Greenland at daily time scales
- 20 from 2003 to 2009, J. Phys. Oceanogr., 46, 141–157, https://doi.org/10.1175/JPO-D-15-0093.1, 2016.
- Münchow, A., Melling, H., and Falkner, K. K.: An observational estimate of volume and freshwater flux leaving the Arctic Ocean through Nares Strait, J. Phys. Oceanogr., 36, 2025–2041, 2006.
- ²⁵ Münchow, A., Falkner, K. K., and Melling, H.: Spatial continuity of measured seawater and tracer fluxes through Nares Strait, a dynamically wide channel bordering the Canadian Archipelago, J. Mar. Res., 65, 759–788, https://doi.org/10.1357/002224007784219048, 2007.
- ³⁰ Mundy, C. J. and Barber, D. G.: On the relationship between spatial patterns of sea-ice type and the mechanisms which create and maintain the North Water (NOW) polynya, Atmos. Ocean 39, 327–341, https://doi.org/10.1080/07055900.2001.9649684, 2001.
- ³⁵ Nürnberg, D., Wollenburg, I., Dethleff, D., Eicken, H., Kassens, H., Letzig, T., Reimnitz, E., and Thiede, J.: Sediments in Arctic sea ice: implications for entrainment, transport and release, Mar. Geol., 119, 185–214, 1994.
- Oakey, G. N. and Damaske, D.: Continuity of basement structures
- and dyke swarms in the Kane Basin region of central Nares Strait constrained by aeromagnetic data, Polarforschung, 74, 51–62, 2004.
- Ó Cofaigh, C. and Dowdeswell, J. A.: Laminated sediments in glacimarine environments: diagnostic criteria for their interpretation, Quaternary Sci. Rev., 20, 1411–1436, 2001.
- Ó Cofaigh, C., Dowdeswell, J. A., and Grobe, H.: Holocene glacimarine sedimentation, inner Scoresby Sund, East Greenland: the influence of fast-flowing scheet outlet glaciers, Mar. Geol., 175, 103–129, 2001.
- ⁵⁰ Osterman, L. E. and Andrews, J. T.: Changes in glacial-marine sedimentation in core HU77-159, Frobisher Bay, Baffin Island, N. W. T.: a record of proximal, distal, and ice-rafting glacial-marine environments; in: Glacial-Marine Sedimentation, edited by: Molnia, B. F., Plenum Press, New York, USA, 451–493, 1983.
 ⁵⁵ 1983.IIS46
- Pfirman, S., Wollenburg, I., Thiede, J., Lange, M.A.: Lithogenic sediment on Artic pack ice: potential aeolian flux and contributions to deep sea sediments, in: Paleoclimatology and Paleometeorology: Modern and Past Pattern of Global Atmospheric

Transport, edited by: Sarnthein, M. and Leinen, M., Kluwer, Dor- 60 drecht, the Netherlands, 463–493, 1989.

- Pienkowski, A. J., England, J. H., Furze, M. F. A., Marret, F., Eynaud, F., Vilks, G., MacLean B., Blasco, S., and Scourse, J. D.: The deglacial to postglacial marine environments of SE Barrow Strait, Canadian Arctic Archipelago, Boreas, 41, 141–179, 65 https://doi.org/10.1111/j.1502-3885.2011.00227.x, 2012.
- Rabe, B., Johnson, H. L., Münchow, A., and Melling, H.: Geostrophic ocean currents and freshwater fluxes across the Canadian polar shelf via Nares Strait, J. Mar. Res., 70, 603–640, 2012.

70

- Reeh, N., Thomsen, H. H., Higgins, A. K., and Weidick, A.: Sea ice and the stability of north and northeast Greenland floating glaciers, Ann. Glaciol., 33, 474–480, 2001.
- Reimer, P. J., Bayliss, E. B. A., Beck, J. W., Blackwell, P. G., Ramsey, C. B., Buck, C. E., Cheng, H., Edwards, R. L., Friedrich, 75 M., Grootes, P. M., Guilderson, T. P., Haflidason, H., Hajdas, I., Hatté, C., Heaton, T. J., Hoffmann, D. L., Hogg, A. G., Hughen, K. A., Kaiser, K. F., Kromer, B., Manning, S. W., Niu, M., Reimer, R. W., Richards, D. A., Scott, A. M., Southon, J. R., Staff, R. A., Turney, C. S. M., and van der Plicht, J.: IntCal13 and MARINE13 radiocarbon age calibration curves 0–5000 years cal. BP., Radiocarbon, 55, 1869–1887, 2013.
- Reusche, M. M., Marcott, S. A., Ceperley, E. G., Barth, A. M., Brook, E. J., Mix, A. C., Caffee, M. W.: Early to Late Holocene surface exposure ages from two marine-terminating ⁸⁵ outlet glaciers in Northwest Greenland. Geophys. Res. Lett., 45, 7028–7039, https://doi.org/10.1029/2018GL078266, 2018.
- Samelson, R. M. and Barbour, P. L.: Low-level winds in Nares Strait: A model-based mesoscale climatology, Mon. Weather Rev., 136, 4746–4759, 2008.
- Stuiver, M., Reimer, P. J., and Reimer, R. W.: CALIB 7.1 [WWW program], available at: http://calib.org
- Svendsen, J. I., Mangerud, J., Elverhøi, A., Solheim, A., and Schüttenhelm, R. T. E.: The Late Weichselian glacial maximum on western Spitsbergen inferred from offshore sediment cores, Mar. 95 Geol., 104, 1–17, 1992.
- Syvitski, J. P. M.: Towards an understanding of sediment deposition on glaciated tinental shelves, Cont. Shelf Res., 11, 897–937, 1991.
- Tjallingii, R., Röhl, U., Kölling, M., and Bickert, T.: Influence of 100 the water content on X-ray fluorescence core-scanning measurements in soft marine sediments, Geochem. Geophy. Geosys. 9 Q02004, https://doi.org/10.1029/2006GC001393, 2007.
- Tushingham, A. M.: On the extent and thickness of the Innuitian Ice Sheet: a postglacial-adjustment approach, Can. J. Earth Sci., 28, 105 231–239, 1990.
- Vare, L. L., Massé, G., Gregory, T. R., Smart, C. W., and Belt, S. T.: Sea ice variations in the central Canadian Arctic Archipelago during the Holocene, Quaternary Sci. Rev., 28, 1354–1366, 2009.
- Vinther, B. M., Clausen, H. B., Johnsen, S. J., Rasmussen, S. O., ¹¹⁰ Andersen, K. K., Buchardt, S. L., Dahl-Jensen, D., Seierstad, I. K., Siggaard-Andersen, M. L., Steffensen, J. P., Svensson, A., Olsen, J., and Heinemeier, J.: A synchronized dating of three Greenland ice cores throughout the Holocene, J. Geophys. Res., 111, D13102, https://doi.org/10.1029/2005JD006921, 2006. ¹¹⁵
- Weltje, G. J. and Tjanllingii, R. Calibration of XRF core scanners for quantitative geochemical logging of sediment cores:

Theory and applications, Earth Planet Sc. Lett. 274, 4238, https://doi.org/10.1016/j.epsl.2008.07.054, 2008.

- Zaragosi, S., Bourillet, J.-F., Eynaud, F., Toucanne, S., Denhard, B., Van Toer, A., and Lanfumey, A.: The impact of the last Euro-
- pean deglaciation on the deep-sea turbidite systems of the Celtic-Armorican margin (Bay of Biscay), Geo-Mar. Lett. 26, 317–329, https://doi.org/10.1007/s00368-006-0048-9, ISSI 1
- Zreda, M., England, J., Phillips, F., Elmore, D., and Sharma, P.: Unblocking of the Nares Strait by Greenland and Ellesmere Ice-Sheet retreat 10000 years ago, Nature, 398, 139–142, 10 https://doi.org/10.1038/18197, 1999.

Remarks from the language copy-editor

CE1 In keeping with the dominant style of the manuscript, Oxford spellings were not applied.

Please note that Figs. 4, 6–8, and Table 2 were edited during copy-editing (adjusted for spelling and punctuation only). Please review the figure content carefully.

Please note that we use ka for ages/dates and kyr for durations. Please check that this has been applied correctly and consistently throughout the paper.

Remarks from the typesetter

- Copernicus Publications collects the DOIs of datasets, videos, samples, model code, and other supplementary/underlying material or resources as well as additional outputs. These assets should be added to the reference list (author(s), title, DOI, and year) and properly cited in the article. If no DOI can be registered, assets can be linked through persistent URLs. This is not seen as best practice and the persistence of the URL must be secured.
- TS2 Please confirm.
- TS3 Please confirm.
- **TS4** Please also add to reference list.
- TS5 Please confirm.
- The composition of Figs. 2–4 and 6–8 has been adjusted to our standards.
- **TS7** Should this be 2008?
- TS8 Please check running title.
- TS9 Please confirm.
- **TS10** Please also add to reference list.
- TS11 Please confirm.
- TS12 Please confirm.
- TSI3 Please confirm.
- TS14 Please confirm.
- TS15 Please confirm.
- **TS16** Should this be "England, 1999"?
- TS17 Was "Dawes, 2004". Please confirm.
- TS18 Please confirm.

Please provide a statement on how your underlying research data can be accessed. If the data are not publicly accessible, a detailed explanation of why this is the case is required. The best way to provide access to data is by depositing them (as well as related metadata) in reliable public data repositories, assigning digital object identifiers (DOIs), and properly citing datasets as individual contributions. Please indicate if different datasets are deposited in different repositories or if data from a third party were used. If no DOI is available, assets can be linked through persistent URLs to the dataset itself (not to the repositories' home page). This is not seen as best practice and the persistence of the URL must be secured.

Copernicus Publications strongly recommends including the section "Author contributions".

Declaration of all potential conflicts of interest is required by us as this is an integral aspect of a transparent record of scientific work. If there are possible conflicts of interest, please state what competing interests are relevant to your work.

- **TS22** Please note that this reference is not mentioned in the text.
- Please provide complete page range or article number with DOI.
- **TS24** Please provide page range or article number with DOI.
- TS25 Please provide volume.
- **TS26** Please update if possible.
- **TS27** Please provide page range or article number with DOI.
- TS28 Please provide volume.
- Please provide volume as well as page range or article number with DOI.
- **TS30** Please note that this reference is not mentioned in the text.
- **TS31** Please note that this reference is not mentioned in the text.
- **TS32** Please note that this reference is not mentioned in the text.
- **IS33** Please provide page range or article number.
- **TS34** Please provide page range or article number with DOI.
- **TS35** Please provide complete page range or article number with DOI.
- **TS36** Please provide volume.

- **TS37** Please check page range.
- **TS38** Please provide volume.
- **TS39** Please check page range.
- **TS40** Please provide complete page range or article number with DOI.
- **TS41** Please provide page range or article number with DOI.
- TS42 Please provide volume.
- **TS43** Please check page range.
- **TS44** Please provide page range or article number with DOI.
- **TS45** Please note that this reference is not mentioned in the text.
- **TS46** Please note that this reference is not mentioned in the text.
- **TS47** Please note that this reference is not mentioned in the text.
- **TS48** Please provide last access date.
- **TS49** Please note that this reference is not mentioned in the text.
- **TS50** Please note that this reference is not mentioned in the text.
- **TS51** DOI does not work. Please check.